

Tender Id No: CUTNCVL20212206

Date:07.10.2021

NOTICE INVITING TENDER (LTE)

The Registrar, Central University of Tamil Nadu (CUTN), Neelakudi campus, Thiruvarur- 610 005 invites sealed tender from contractors having civil experience, working in Central/ State Government/ Public sector undertakings (PSU)/ Autonomous Organisations of the Central/ State Government.

01	Tender Ref. no	:	CUTN/ENGG/CVL/Tender/2021-22/06
02	Name of work	:	Repair and renovation – Toilet – Civil at Central University of Tamil Nadu Thiruvarur.
04	Earnest Money Deposit (EMD) fee	:	Bid Security Declaration (EMD) as per prescribed format (<i>Annexure-A</i>) or NSIC/MSME/SSI Registration No. (<i>If available</i>)
03	Period of Work	:	05 days (From the date of commencement of the work which will be calculated from the date of handing over of site to the contractor.)
04	Defects Liability period (DLP)	:	06 months (From the date of actual completion of entire work and handing over to CUTN, Thiruvarur)
05	Last date & time for receipt of Tenders	:	11.10.2021 upto15:00 Hrs (Office time)
06	Date & time of opening of Tender	:	Admin building, CUTN. 11.10.2021 upto15:30 Hrs (Office time)
07	Address for submission of Tender	:	The Registrar , Central University of Tamil Nadu, Neelakudi campus, Thiruvarur, Tamil Nadu - 610 005. With a mark of kind attention to: The Executive Engineer, Engineering section, CUTN, Thiruvarur.

- 1) Certificate of Enlistment/ registration certificate in any government organisation related to Civil works should be submitted.
- 2) The rates, amount should be filled in the Bill of Quantities (BOQ) enclosed with this and placed in a sealed cover by super scribing the name of the work in the cover as mentioned above.
- 3) Bidders are advised to regularly check our website (www.cutn.ac.in) for any corrigendum/amendments till the opening of tender. The notice with BOQ can also be downloaded in the University website. Tenders received after due date/time will not be considered under any circumstances.
- 4) The successful tenderer shall deposit an amount equal to 3 % of the tendered and accepted value of the work (without limit) as performance guarantee in the forms of: Demand Draft or A scheduled bank guarantee or Banker's Cheque. The time allowed for submission of the performance guarantee by the contractor shall be decided by the CUTN approving authority for a period ranging from 2 to 4 days of issue of the Letter of Acceptance, depending upon the magnitude and/or urgency of the work. The Performance Guarantee shall be initially valid up to the stipulated date of completion and defect liability period plus sixty (60) days plus beyond that. The Performance Guarantee will be

returned to the contractor after 60 days on successful completion of the contract and handing over to CUTN, Thiruvarur including extension period (if awarded) plus defects liability period.

- 5) Payment will be made on submission of bill on satisfactory completion of works. The Last & final bill complete in all respect shall be submitted by the bidder within Sixty (60) days from the date of completion of work. The Contractor should submit the last & final bill along with a "NIL CLAIM CERTIFICATE"
- 6) Items of work other than those mentioned in the Bill of Quantities (Tender Schedule) attached hereto will be carried out at the rates to be fixed by this University as per relevant clauses of CPWD Works Manual. Tender quantity is only approximate and liable for variation without entitling the tenderer to any compensation, till the total value of contract vary by more than 30% (thirty percentages). All the materials to be used in the work and the nature of work shall conform to the respective BIS, CPWD and National Building Organisation, Standard Specifications forming part of "Delhi standard schedule of rates" specifications. All the materials to be used in the works and nature of work shall conform to respective CPWD, BIS and National Buildings Organisation Standard Specifications and shall be got approved by the Engineer – in – charge before actual incorporation in the works. The daily progress of work shall be maintained according to the work is to be finished.
- 7) In case of contractor's failing to complete the work within the period specified the contractor shall be liable to penalty @1.5% per week of delay and total amount of compensation for delay to be recovered under this condition shall not exceed 10% of the contract value.
- 8) Honourable Vice Chancellor, CUTN, Thiruvarur/The Registrar, CUTN, Thiruvarur reserves the right to accept or reject all or any of the applications and to annul the qualification process / tender process at any time without assigning any reason or incurring any liability to the applicants. Any dispute or claim arising out of/relating to this Contractor the breach, termination or the invalidity thereof, shall be settled by the Hon'ble Courts of Justice at Thiruvarur.
- 9) The water charges will be recovered at the rate of 1% of the executed value, if water is used. Charges for electricity should paid to University as per meter readings & TNEB rates or fixed amount as per the direction of Engineer In charge, if electricity is consumed. Labour welfare cess of 1% of bill value will also be recovered from the bills and submitted to the authorities of the department.

Special condition:-

- 10) Rates are including the cost of all the materials, labour, T&P, scaffolding etc. for the execution and completion of the work. Rates are applicable for all heights and levels of the buildings. The cleaning of all the white wash and painting spots over the doors, windows, floors, glass, electric switches & fixtures, is the responsibility of the Contractor nothing extra on account of this would be paid. If the contractor fails to clean these spots it would be got cleaned departmentally and expenditure incurred would be debited to the contractors account. All the safety measures which are for safe execution of the work is in the scope of the contractor. If any accident/ mishappening occurred during the execution of work at site the contractor shall be solely responsible for the same. The work shall be taken up strictly as per the latest IS codes, consumption factors and CPWD specifications with updated latest amendments.
- 11) **Location** : 200 seater Girls Hostel, CUTN

Note: Contract Agreement and Integrity pact will be signed between CUTN and successful bidder before issuing of work order.

The Registrar
Central University of Tamil Nadu, Thiruvarur

BID SECURITY DECLARATION FORM
(EMD)

(In lieu of EMD, as per the directions of MOF, DOE, GOI. OM No.F.9/4/2020-PPD dated 12.11.2020)

Tender Ref No: CUTN/ENGG/CVL/Tender/2021-22/06

Date: _____

To

The Registrar,
Central University of Tamil Nadu,
Thiruvarur.

Sir/Madam,

I/We, the undersigned declare that,

I/We understand that according to your conditions, bids must be supported by a Bid Security Declaration.

I/We accept that I/We may be disqualified from bidding for any contract with you for a period of one year from the date of notification if I am/We are in a breach of any obligation under the bid conditions, because I/We

- (a) have withdrawn/modified/amended, impairs or derogates from the tender, my/our Bid during the period of bid validity specified in the form of Bid; or
- (b) having been notified of the acceptance of our Bid by the purchaser during the period of bid validity (i) fail or refuse to execute the contract, if required, or (ii) fail or refuse to furnish the performance security, in accordance with the instructions to Bidders.

I/We understand this Bid Securing Declaration shall cease to be valid if I am/we are not the successful Bidder, upon the earlier of (i) the receipt of your notification of the name of the successful Bidder; or (ii) thirty days after the expiration of the validity of my/our Bid.

Signature: _____

In the capacity of: _____

Name: _____

Duly authorized to sign the bid for an on behalf of M/s. _____

Dated on _____ day of _____

Corporate Seal:

(Note: In case of a Joint Venture, the Bid Securing Declaration must be in the name of all partners to the Joint Venture that submits the bid)

FINANCIAL BID

Name of the work: Repair and renovation – Toilet – Civil at Central University of Tamil Nadu Thiruvavur.

Item No.	DSR 2018	Description of work	Quantity	Unit	Rate in figures (Rs.)	Rate in words (Rs)	Amount in figures (Rs.)
<i>(A)</i>		<i>(B)</i>	<i>(C)</i>	<i>(D)</i>	<i>(E)</i>	<i>(F)</i>	<i>(G) = (C) X (E)</i>
1	8.31	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineerin- Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	5.00	Sq.m			
2	9.105	Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with					

		nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks, Galvanised M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each with zinc coating of 120 gms/sqm(both side inclusive)) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacture's specification and direction of engineer in charge all complete.					
2.1	9.105.2	75mm overall thickness partition with 12.5 mm thick double skin tapered edged plain Gypsum plaster board conforming to IS: 2095: (part I) 2011 (Board with BIS Certification marks)	4.00	Sq.m			
3	13.1	12 mm cement plaster:					
3.1	13.1.1	1:4 (1 cement : 4 fine sand)	15.00	Sq.m			
4	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	403.00	Sq.m			
5	13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	1210.00	Sq.m			

6	13.90	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade :					
6.1	13.90.1	Old work (one or more coats)	1613.00	Sq.m			
7	13.99	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :					
7.1	13.99.1	One or more coats on old work.	120.00	Sq.m			
8	13.112	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade					
8.1	13.112.2	Old work (one or more coats applied @ 0.83 ltr/10 sqm).	100.00	Sq.m			
9	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.					
9.1	14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand)	50.00	Sq.m			
10	17.32	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :					
10.1	17.32.2	Rectangular shape 453x357 mm	12.00	Each			

10.2	17.32.4	Rectangular shape 1500x450 mm	18.00	Each			
11	LMR	Applying water proofing course, including scrapping, dampblock chemical (2 coats), Putty (2 coat), primer(1 coat),emulsion (2 Coat),as per the direction of Engineer in charge.	81.00	Sq.m			
Total Amount of Rupees (Excluding GST)							
GST in %					GST in Rupees.		
Total Amount of Rupees (Including GST) and all applicable taxes.							
Rupees words).....							
<p>Note: 1. All other requirements, scope of work as mentioned in this tender document should be considered before quoting.</p> <p>1. I/We declare that the above quoted rate inclusive of all Charges & Taxes are firm throughout the entire period of contract and no cost escalation/ no variation will be paid on any account.</p>							

Signature of Bidder/Contractor
with Seal